

# Tree Survey Spreadsheet at Church Farm House Church Lane Yapton BN18 0EP

| No | Species                 | Height | Ø at 1.5m | Spread | Crown     | Age | Condition and                                                 | Removal | ERC | BS    | RPA   |
|----|-------------------------|--------|-----------|--------|-----------|-----|---------------------------------------------------------------|---------|-----|-------|-------|
|    |                         |        |           | NSEW   | clearance |     | Recommendations                                               |         |     | Grade |       |
| T1 | Lime                    | 22     | 720       | 12.0Ø  | 4mN       | M   | Physiological Condition: Good                                 | N       | >40 | A2    | 8.64  |
|    | <i>Tilia x europaea</i> |        |           |        |           |     | Structural Condition: Good                                    | CB      | B   |       |       |
|    |                         |        |           |        |           |     | Public Amenity Value: High                                    |         |     |       |       |
|    |                         |        |           |        |           |     | Inspection Limitations: Abundant epicormic growth at the base |         |     |       |       |
|    |                         |        |           |        |           |     | <b>Recommend:</b> Remove epicormic growth at the base         |         |     |       |       |
| T2 | Lime                    | 22     | 905       | 12.0Ø  | 8mN       | M   | Physiological Condition: Good                                 | N       | >40 | A2    | 10.85 |
|    | <i>Tilia x europaea</i> |        |           |        |           |     | Structural Condition: Good                                    | CB      | B   |       |       |
|    |                         |        |           |        |           |     | Public Amenity Value: High                                    |         |     |       |       |
|    |                         |        |           |        |           |     | Inspection Limitations: Abundant epicormic growth at the base |         |     |       |       |
|    |                         |        |           |        |           |     | <b>Recommend:</b> Remove epicormic growth at the base         |         |     |       |       |
| T3 | Lime                    | 22     | 725       | 12.0Ø  | 8mN       | M   | Physiological Condition: Good                                 | N       | >40 | A2    | 8.7   |
|    | <i>Tilia x europaea</i> |        |           |        |           |     | Structural Condition: Good                                    | CB      | B   |       |       |
|    |                         |        |           |        |           |     | Public Amenity Value: High                                    |         |     |       |       |
|    |                         |        |           |        |           |     | Inspection Limitations: Abundant epicormic growth at the base |         |     |       |       |
|    |                         |        |           |        |           |     | <b>Recommend:</b> Remove epicormic growth at the base         |         |     |       |       |
| T4 | Lime                    | 22     | 645       | 12.0Ø  | 10mN      | M   | Physiological Condition: Good                                 | N       | >40 | A2    | 7.74  |
|    | <i>Tilia x europaea</i> |        |           |        |           |     | Structural Condition: Good                                    | CB      | B   |       |       |
|    |                         |        |           |        |           |     | Public Amenity Value: High                                    |         |     |       |       |
|    |                         |        |           |        |           |     | Inspection Limitations: Abundant epicormic growth at the base |         |     |       |       |
|    |                         |        |           |        |           |     | <b>Recommend:</b> Remove epicormic growth at the base         |         |     |       |       |
| T5 | Lime                    | 22     | 810       | 12.0Ø  | 10mN      | M   | Physiological Condition: Good                                 | N       | >40 | A2    | 9.72  |
|    | <i>Tilia x europaea</i> |        |           |        |           |     | Structural Condition: Good                                    | CB      | B   |       |       |
|    |                         |        |           |        |           |     | Public Amenity Value: High                                    |         |     |       |       |
|    |                         |        |           |        |           |     | Inspection Limitations: Abundant epicormic growth at the base |         |     |       |       |
|    |                         |        |           |        |           |     | <b>Recommend:</b> Remove epicormic growth at the base         |         |     |       |       |
| T6 | Lime                    | 22     | 495       | 9.0Ø   | 8mS       | M   | Physiological Condition: Good                                 | N       | >40 | A2    | 5.94  |
|    | <i>Tilia x europaea</i> |        |           |        |           |     | Structural Condition: Good                                    | CB      | B   |       |       |
|    |                         |        |           |        |           |     | Public Amenity Value: High                                    |         |     |       |       |
|    |                         |        |           |        |           |     | Inspection Limitations: Abundant epicormic growth at the base |         |     |       |       |
|    |                         |        |           |        |           |     | <b>Recommend:</b> Remove epicormic growth at the base         |         |     |       |       |
| T7 | Lime                    | 22     | 680       | 14.0Ø  | 8mN       | M   | Physiological Condition: Good                                 | N       | >40 | A2    | 8.16  |
|    | <i>Tilia x europaea</i> |        |           |        |           |     | Structural Condition: Good                                    | CB      | B   |       |       |
|    |                         |        |           |        |           |     | Public Amenity Value: High                                    |         |     |       |       |

# Tree Survey Spreadsheet at Church Farm House Church Lane Yapton BN18 0EP

|            |                               |    |         |         |       |    |                                                               |     |     |    |      |
|------------|-------------------------------|----|---------|---------|-------|----|---------------------------------------------------------------|-----|-----|----|------|
|            |                               |    |         |         |       |    | Inspection Limitations: Abundant epicormic growth at the base |     |     |    |      |
|            |                               |    |         |         |       |    | <b>Recommend:</b> Remove epicormic growth at the base         |     |     |    |      |
| <b>T8</b>  | Oak                           | 12 | 370     | 11.0Ø   | 2mS   | SM | Physiological Condition: Good                                 | N   | >40 | A2 | 4.44 |
|            | <i>Quercus robur</i>          |    |         |         |       |    | Structural Condition: Good                                    | CL4 | B   |    |      |
|            |                               |    |         |         |       |    | Public Amenity Value: Medium                                  |     |     |    |      |
|            |                               |    |         |         |       |    | Inspection Limitations: None                                  |     |     |    |      |
|            |                               |    |         |         |       |    | <b>Recommend:</b> Lift tree canopy to 4m AGL for works access |     |     |    |      |
| <b>T9</b>  | Holm Oak                      | 13 | 240+170 | 5.0Ø    | 2mS   | SM | Physiological Condition: Good                                 | N   | >40 | A2 | 3.53 |
|            | <i>Quercus ilex</i>           |    |         |         |       |    | Structural Condition: Good                                    |     |     |    |      |
|            |                               |    |         |         |       |    | Public Amenity Value: Low                                     |     |     |    |      |
|            |                               |    |         |         |       |    | Inspection Limitations: None                                  |     |     |    |      |
|            |                               |    |         |         |       |    | Bifurcates @ 1.3m                                             |     |     |    |      |
| <b>T10</b> | Oak                           | 15 | 300     | 10.0Ø   | 3mS   | SM | Physiological Condition: Good                                 | N   | >40 | A2 | 3.6  |
|            | <i>Quercus robur</i>          |    |         |         |       |    | Structural Condition: Good                                    |     |     |    |      |
|            |                               |    |         |         |       |    | Public Amenity Value: Low                                     |     |     |    |      |
|            |                               |    |         |         |       |    | Inspection Limitations: None                                  |     |     |    |      |
| <b>T11</b> | Walnut                        | 12 | 285     | 7.0Ø    | 2mE   | SM | Physiological Condition: Good                                 | N   | >40 | A2 | 3.42 |
|            | <i>Juglans regia</i>          |    |         |         |       |    | Structural Condition: Good                                    |     |     |    |      |
|            |                               |    |         |         |       |    | Public Amenity Value: Low                                     |     |     |    |      |
|            |                               |    |         |         |       |    | Inspection Limitations: None                                  |     |     |    |      |
| <b>T12</b> | Norway Maple                  | 14 | 200+180 | 8.0Ø    | 1.2mE | SM | Physiological Condition: Good                                 | N   | >40 | A2 | 5.46 |
|            | <i>Acer platanooides</i>      |    | 190+295 |         |       |    | Structural Condition: Good                                    |     |     |    |      |
|            | <i>Crimson King'</i>          |    | 110     |         |       |    | Public Amenity Value: Low                                     |     |     |    |      |
|            |                               |    |         |         |       |    | Inspection Limitations: None                                  |     |     |    |      |
|            |                               |    |         |         |       |    | Bifurcates @ 1.2m                                             |     |     |    |      |
| <b>T13</b> | Apple                         | 10 | 325+295 | 4/3/5/4 | 2mE   | OM | Physiological Condition: Good                                 | N   | >10 | C2 | 5.42 |
|            | <i>Malus domestica</i>        |    | 190     |         |       |    | Structural Condition: Fair                                    |     |     |    |      |
|            |                               |    |         |         |       |    | Public Amenity Value: Low                                     |     |     |    |      |
|            |                               |    |         |         |       |    | Inspection Limitations: None                                  |     |     |    |      |
|            |                               |    |         |         |       |    | Veteran fruit tree with open splayed scaffold and stems       |     |     |    |      |
|            |                               |    |         |         |       |    | leaning outwards 15-45°. Old wounds present some decay.       |     |     |    |      |
|            |                               |    |         |         |       |    | Heavy crop with good leaf cover                               |     |     |    |      |
| <b>T14</b> | Horse Chestnut                | 12 | 370     | 10.0Ø   | 3mN   | EM | Physiological Condition: Fair                                 | N   | >20 | B2 | 4.44 |
|            | <i>Aesculus hippocastanum</i> |    |         |         |       |    | Structural Condition: Good                                    |     |     |    |      |
|            |                               |    |         |         |       |    | Public Amenity Value: Low                                     |     |     |    |      |

# Tree Survey Spreadsheet at Church Farm House Church Lane Yapton BN18 0EP

|            |                                                                 |    |               |         |     |    |                                                          |   |     |           |      |
|------------|-----------------------------------------------------------------|----|---------------|---------|-----|----|----------------------------------------------------------|---|-----|-----------|------|
|            |                                                                 |    |               |         |     |    | Inspection Limitations: None                             |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Barked trunk g/l-1m NW                                   |   |     |           |      |
| <b>T15</b> | Aspen<br><i>Populus tremula</i>                                 | 15 | 410           | 10.0Ø   | 2mE | EM | Physiological Condition: Good                            | N | >20 | <b>B2</b> | 4.92 |
|            |                                                                 |    |               |         |     |    | Structural Condition: Fair                               |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Public Amenity Value: Low                                |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Inspection Limitations: None                             |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Lifted to 1.8 S side                                     |   |     |           |      |
| <b>T16</b> | Beech<br><i>Fagus sylvatica</i>                                 | 16 | 240           | 10.0Ø   | 2mS | EM | Physiological Condition: Good                            | N | >40 | <b>A2</b> | 2.88 |
|            |                                                                 |    |               |         |     |    | Structural Condition: Good                               |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Public Amenity Value: Low                                |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Inspection Limitations: None                             |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Lifted to 2m                                             |   |     |           |      |
| <b>T17</b> | Oak<br><i>Quercus robor</i>                                     | 16 | 360           | 10.0Ø   | 2mS | EM | Physiological Condition: Good                            | N | >40 | <b>A2</b> | 4.32 |
|            |                                                                 |    |               |         |     |    | Structural Condition: Good                               |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Public Amenity Value: Low                                |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Inspection Limitations: None                             |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Lifted to 2m                                             |   |     |           |      |
| <b>T18</b> | Norway Maple<br><i>Acer platanoides</i><br><i>Crimson King'</i> | 13 | 400           | 9.0Ø    | 2mS | EM | Physiological Condition: Good                            | N | >40 | <b>A2</b> | 4.8  |
|            |                                                                 |    |               |         |     |    | Structural Condition: Good                               |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Public Amenity Value: Low                                |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Inspection Limitations: None                             |   |     |           |      |
| <b>T19</b> | Apple<br><i>Malus domestica</i>                                 | 9  | 225 (1)+310   | 3/3/4/2 | 2mN | OM | Physiological Condition: Good                            | N | >10 | <b>C2</b> | 4.59 |
|            |                                                                 |    |               |         |     |    | Structural Condition: Fair                               |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Public Amenity Value: Low                                |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Inspection Limitations: None                             |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Veteran fruit tree with open splayed scaffold and stem   |   |     |           |      |
|            |                                                                 |    |               |         |     |    | (1) leaning outwards 45°. Old wounds present some decay. |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Past prediction of 2 main stems to 1.2m.                 |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Heavy crop with good leaf cover                          |   |     |           |      |
| <b>T20</b> | Beech<br><i>Fagus sylvatica</i>                                 | 15 | 180           | 6.0Ø    | 2mS | SM | Physiological Condition: Good                            | N | >40 | <b>A2</b> | 2.16 |
|            |                                                                 |    |               |         |     |    | Structural Condition: Good                               |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Public Amenity Value: Low                                |   |     |           |      |
|            |                                                                 |    |               |         |     |    | Inspection Limitations: None                             |   |     |           |      |
| <b>T21</b> | Oak<br><i>Quercus robor</i>                                     | 12 | 230+140<br>80 | 5.0Ø    | g/l | EM | Physiological Condition: Good                            | N | >40 | <b>B2</b> | 3.37 |
|            |                                                                 |    |               |         |     |    | Structural Condition: Fair                               |   |     |           |      |

# Tree Survey Spreadsheet at Church Farm House Church Lane Yapton BN18 0EP

|            |                                  |    |          |         |     |    |                                                               |     |          |           |      |
|------------|----------------------------------|----|----------|---------|-----|----|---------------------------------------------------------------|-----|----------|-----------|------|
|            |                                  |    |          |         |     |    | Public Amenity Value: Low                                     |     |          |           |      |
|            |                                  |    |          |         |     |    | Inspection Limitations: None                                  |     |          |           |      |
|            |                                  |    |          |         |     |    | T21 and T22 planted 3m apart                                  |     |          |           |      |
| <b>T22</b> | Oak                              | 14 | 170+130  | 5.0Ø    | g/l | EM | Physiological Condition: Good                                 | N   | >40      | <b>B2</b> | 2.95 |
|            | <i>Quercus robur</i>             |    | 100+70   |         |     |    | Structural Condition: Fair                                    |     |          |           |      |
|            |                                  |    |          |         |     |    | Public Amenity Value: Low                                     |     |          |           |      |
|            |                                  |    |          |         |     |    | Inspection Limitations: None                                  |     |          |           |      |
| <b>T23</b> | Plum                             | 9  | 70       | 3.0Ø    | 2mS | SM | Physiological Condition: Fair                                 | N   | >10      | <b>C2</b> | 0.84 |
|            | <i>Prunus domestica</i>          |    |          |         |     |    | Structural Condition: Poor                                    | CC  | <b>B</b> |           |      |
|            |                                  |    |          |         |     |    | Public Amenity Value: Low                                     |     |          |           |      |
|            |                                  |    |          |         |     |    | Inspection Limitations: Brambles                              |     |          |           |      |
|            |                                  |    |          |         |     |    | <b>Recommend:</b> Remove brambles                             |     |          |           |      |
| <b>T24</b> | Plum                             | 9  | 50+60+70 | 1/1/2/2 | 1mS | SM | Physiological Condition: Fair                                 | N   | >10      | <b>C2</b> | 1.26 |
|            | <i>Prunus domestica</i>          |    |          |         |     |    | Structural Condition: Poor                                    |     |          |           |      |
|            |                                  |    |          |         |     |    | Public Amenity Value: Low                                     |     |          |           |      |
|            |                                  |    |          |         |     |    | Inspection Limitations: None                                  |     |          |           |      |
| <b>T25</b> | Beech                            | 9  | 85       | 3.0Ø    | 2mN | SM | Physiological Condition: Good                                 | N   | >40      | <b>A2</b> | 1.02 |
|            | <i>Fagus sylvatica</i>           |    |          |         |     |    | Structural Condition: Good                                    |     |          |           |      |
|            |                                  |    |          |         |     |    | Public Amenity Value: Low                                     |     |          |           |      |
|            |                                  |    |          |         |     |    | Inspection Limitations: None                                  |     |          |           |      |
| <b>T26</b> | Beech                            | 9  | 85       | 3.0Ø    | 2mN | SM | Physiological Condition: Good                                 | N   | >40      | <b>A2</b> | 1.02 |
|            | <i>Fagus sylvatica</i>           |    |          |         |     |    | Structural Condition: Good                                    |     |          |           |      |
|            |                                  |    |          |         |     |    | Public Amenity Value: Low                                     |     |          |           |      |
|            |                                  |    |          |         |     |    | Inspection Limitations: None                                  |     |          |           |      |
| <b>T27</b> | Indian Bean tree                 | 15 | 485+425  | 7/6/6/5 | 2mS | M  | Physiological Condition: Good                                 | N   | >40      | <b>B2</b> | 7.74 |
|            | <i>Catalpa bignonioides</i>      |    |          |         |     |    | Structural Condition: Fair                                    | CL4 | <b>B</b> |           |      |
|            |                                  |    |          |         |     |    | Public Amenity Value: Low                                     |     |          |           |      |
|            |                                  |    |          |         |     |    | Inspection Limitations: None                                  |     |          |           |      |
|            |                                  |    |          |         |     |    | Bifurcates @0.25 into two main stems that lean outwards       |     |          |           |      |
|            |                                  |    |          |         |     |    | <b>Recommend:</b> Lift tree canopy to 4m AGL for works access |     |          |           |      |
| <b>T28</b> | Beech                            | 16 | 375      | 16.0Ø   | 5mN | EM | Physiological Condition: Good                                 | N   | >40      | <b>A2</b> | 4.5  |
|            | <i>Fagus sylvatica</i> 'Pendula' |    |          |         |     |    | Structural Condition: Good                                    | CL4 | <b>B</b> |           |      |
|            |                                  |    |          |         |     |    | Public Amenity Value: Low                                     |     |          |           |      |
|            |                                  |    |          |         |     |    | Inspection Limitations: None                                  |     |          |           |      |
|            |                                  |    |          |         |     |    | <b>Recommend:</b> Lift tree canopy to 4m AGL for works access |     |          |           |      |

Tree Survey Spreadsheet at Church Farm House Church Lane Yapton BN18 0EP

[illegible]