Planting schedule- Trees

Trees

Species	Specification	Qty.
Acer campestre 'Streetwise'	14-16cm girth; 4-4.5m ht.;clear stem to 2m; BR or CG	2 No.
Malus trilobata	12-14cm girth; 3.5-4.25m ht.; clear stem to 1.75-2m; BR or CG	5 No.
Prunus padus 'Albertii'	12-14cm girth; 3.5-4.25m ht.; clear stem to 1.75-2m; BR or CG	8 No.
Pyrus calleryana 'Chanticleer'	14-16cm girth; 4-4.5m ht; BR or CG	9 No.
Quercus robur	20-25cm girth; 5-5.5m ht; BR or CG	1 No.
Sorbus torminalis	12-14cm girth; 3.5-4.25m ht.; clear stem to 1.75-2m; BR or CG	3 No.

Fruit Trees

Species	Specification	Qty.
Malus 'Bramley's Seedling'	M26 2-5 years 1.5m ht min.	2 No.
Malus 'Cox's Orange Pippin'	M26 2-5 years 1.5m ht min.	2 No.
Malus 'Egremont Russet'	M26 2-5 years 1.5m ht min.	1 No.
Malus 'King of the Pippins'	M26 2-5 years 1.5m ht min.	1 No.
Malus 'Red Miller's Seedling'	M26 2-5 years 1.5m ht min.	2 No.

Mixed native hedge

Species	Common name	% of mix	Specification
Acer campestre	Field maple	20	80-100cm ht. BR
Corylus avellana	Hazel	20	80-100cm ht. BR
Crataegus monogyna	Hawthorn	40	80-100cm ht. BR
Ilex aquifolium	Holly	5	60-80cm ht. CG or bagged
Prunus spinosa	Blackthorn	15	80-100cm ht. BR

Clipped hedges to front gardens

Species	Common name	Specification
Carpinus betulus	Hornbeam	80-100cm ht. BR
Ligustrum ovalifolium	Oval-leafed privet	80-100cm ht. BR

Mixed native shrub

Species	Common name	% of mix	Specification
Cornus sanguinea	Common dogwood	25	80-100cm ht. BR
Corylus avellana	Hazel	20	80-100cm ht. BR
Crataegus monogyna	Hawthorn	20	80-100cm ht. BR
Ilex aquifolium	Holly	5	60-80cm ht. CG or bagged
Sambucus nigra	Elder	10	80-100cm ht. BR
Viburnum opulus	Guelder rose	20	80-100cm ht. BR

Indicative ornamental planting to private front gardens and amenity spaces

Species	Density	Size
Anemone x hybrid 'Honorine Jobert'	5/m2	2L CG
Berberis thunbergii f. atropurpurea	4/m2	3L CG
Bergenia cordifolia ssp.	6/m2	2L CG
Cornus 'Midwinter Fire'	3/m2	5L CG
Cotoneaster dammeri	6/m2	3L CG
Digitalis purpurea	6/m2	2L CG
Dryopteris filix-mas	5/m2	2L CG
Euonymus fortunei 'Emerald Gaiety'	5/m2	3L CG
Euphorbia amygdaloides var. robbiae	5/m2	2L CG
Fatsia japonica	4/m2	3L CG
Geranium macrorrhizum 'Album'	5/m2	2L CG
Hebe sp.	5/m2	3L CG
Helleborus foetidus	5/m2	2L CG
Hypericum 'Hidcote'	4/m2	3L CG
Lavandula angustifolia 'Munstead'	5/m2	3L CG
Lonicera pileata	4/m2	3L CG
Miscanthus sp.	4/m2	2L CG
Nassella/Stipa tenuissima	4/m2	2L CG
Prunus laurocerasus 'Otto Luyken'	5/m2	3L CG
Rosa 'Penelope'	3/m2	2L CG or bagged
Rosmarinus officinalis 'Miss Jessopp's Upright'	5/m2	3L CG
Skimmia confusa 'Kew Green'	5/m2	3L CG
Viburnum davidii	5.m2	3L CG
Viburnum tinus	3/m2	5L CG
Vinca minor ssp.	6/m2	2L CG

Indicative climbers

Species	Density	Size
Clematis montana ssp.	Counted	10L CG 3x canes
Lonicera periclymenum 'Belgica'	Counted	10L CG 3x canes
Pyracantha 'Saphyr Red'	Counted	10L CG 3x canes

Bulbs to amenity areas

Species	Density	Size
Crocus tommasinianis	30/m2	Grade 5 / 7
Narcissus pseudonarcissus	25/m2	Grade 5 / 6

0m 10m 20m

north

- All dimensions in millimetres unless otherwise indicated. All levels in metres relative to Ordnance Datum and are positive (AOD) unless otherwise indicated.
- Figure dimensions only to be taken from this drawing, do not scale. Dimensions to be checked on site.
- For civil and structural matters including existing and proposed services, sub-base construction and site structures (including retaining walls over 900mm height) refer to information by others.
- The original version of this drawing was produced in colour - monochrome copies should not be relied upon to accurately reflect all drawing elements.
- This drawing has been prepared for planning purposes only and should not be used for quantification, tender or construction.

Site boundary

Existing tree to be retained and protected in accordance with BS 5837:2012 - refer to arboricultural report by Barrell.

Proposed surfaces

Bitumen macadam road surface with standard and dropped kerbs where required.

Bitumen macadam road surface with standard and dropped kerbs where required.

Concrete block paving to shared surfaces, laid herringbone. Surface colour: TBC.

Concrete block paving to driveways and parking areas, laid herringbone. Surface colour: TBC. Bay delineation in contrasting colour block.

Concrete slab paving to paths and patios. Riven and textured finish. Surface colour: Buff

Mulch

Hoggin public footpath with grass verges

Grasscrete

Proposed boundary treatments

1.8m h closeboard timber fence with matching single gate as required. Fences to have labeled 'hedgehog holes' approx. 13cm/13cm to allow interconnectivity between gardens (www.hedgehogstreet.org). Shown offset from boundary for clarity where necessary .

1.2m h cleft timber post and rail fence with single gate where required and dog-proof mesh

1.8m h weldmesh fence to allotments to match existing

1.8m h brick garden wall (to architects design) with single timber gate where required.

Timber posts to prevent informal parking on grass verges

Proposed soft landscaping

Deciduous trees (including fruit trees)

0.9m h clipped hedge

0.9m h native hedge

Native shrub mix

Shrub and herbaceous planting to private and communal gardens

Species-rich wildflower meadow

Amenity grass (turf or seeded)

Climbers

Bulbs in grass

SPECIFICATION NOTES

1. General.
This plan to be read in conjunction with the following documents:
- Arboricultural report byBarrell Tree Consultancy

2. General landscaping.
i. Existing levels to be preserved around retained existing trees and vegetation. Existing trees and vegetation to be retained are to be protected in accordance with BS5837: 2012 during construction or as detailed in Tree Plan 16371-BT2 by Barrell Tree Consultancy.
ii. All landscape works to be undertaken by competent persons, with appropriate training and equipment.
iii. All arisings to be removed from site at contractor's expense unless noted otherwise (e.g. woodchip, gravel, topsoil).

3. Services.
The contractor must ascertain for himself/herself the exact location of underground services before commencing work.

4. Soil Materials Generally.
i. Purity: Soils shall be free from roots, stolons, rhizomes, propagules of perennial or invasive weeds couch grass, bindweed, docks, Japanese knotweed, giant hogweed and horsetail/marestail (Equisetum avense).
ii. Foreign matter: On visual inspection, free from non-soil material, brick and other building materials and wastes, sharps, and any other foreign matter or material or substance that would render the soil or soil ameliorant unsuitable for use.
iii. Contamination: Do not use topsoil, subsoil, sand or compost contaminated with rubbish or other materials that are:
- Corrosive, explosive or flammable;
- Hazardous to human or animal life;
- Detrimental to healthy plant growth.

iv. Give notice: If any evidence or symptoms of soil contamination are discovered on the site or in topsoil, subsoil, sand or compost or other planting media to be used.

5. Soil testing
Each soil source (imported and site-won subsoil and topsoil - see items 6-9 below) shall be analysed by Tim O'Hare Associates, Howbery Park, Wallingford, Oxon OX10 8BA, Tel: 01491 822653, Email: info@toha.co.uk, www.toha.co.uk (or equivalent approved).

6. Subsoil for general planting areas (sample of site-won and/or imported subsoil to be sent for testing to check compliance with parameters below)
Provide subsoil as necessary to make up deficiency on site. Natural or manufactured subsoil (from approved source) will be acceptable (within parameters given below). Subsoil to be tested to determine suitability for proposed use for planting; test report to be submitted for approval and to enable amelioration recommendations. Subsoil should be free from commonly tested contaminants, including asbestos. Subsoil parameters to be within the following:

Parameter	Unit	Lower Limit	Upper Limit
Clay (<0.002mm)	%	5	35
Silt (0.002-0.05mm)	%	0	35
Sand (0.05-2.0mm) of which at least 40% shall fall into fine to medium sand range	%	50	90
Stones (2-50mm)	%DW	--	50
Stones (>50mm)	%DW	--	0
pH Value	Unit	5.5	8.5*
Electrical Conductivity (1:2.5 water extract)	µS/cm	--	1500
Electrical Conductivity (CaSO4 extract)	µS/cm	--	2800
Exchangeable Sodium Percentage	%	--	15
Organic Matter	%	--	1.5

*IF AN ACIDIC SITE RANGE SHOULD BE 4.5-6.5 IF ALKALINE 7.5-8.5

7. Subsoil for tree pits (sample of site-won and/or imported subsoil to be sent for testing to check compliance with parameters below)
Provide subsoil as necessary to make up deficiency on site. Natural or manufactured subsoil (from approved source) will be acceptable (within parameters given below). Subsoil to be tested to determine suitability for proposed use; test report to be submitted for approval and to enable amelioration recommendations. Subsoil should be free from commonly tested contaminants, including asbestos. Subsoil parameters to be within the following:

Parameter	Unit	Lower Limit	Upper Limit
Clay (<0.002mm)	%	5	18
Silt (0.002-0.05mm)	%	0	25
Sand (0.05-2.0mm) of which at least 40% shall fall into fine to medium sand range	%	60	90
Stones (2-50mm)	% dry wt.	--	50
Stones (>50mm)	% dry wt.	--	0
pH Value	Unit	5.5	8.5*
Electrical Conductivity (1:2.5 water extract)	µS/cm	--	1500
Electrical Conductivity (CaSO4 extract)	µS/cm	--	2800
Exchangeable Sodium Percentage	%	--	15
Organic Matter	%	--	1.5

*IF AN ACIDIC SITE RANGE SHOULD BE 4.5-6.5 IF ALKALINE 7.5-8.5

8. Topsoil for general landscapes (sample of site-won and/or imported topsoil to be sent for testing to check compliance with parameters below and to inform any necessary amelioration - see 10. below)
Existing topsoil to be stripped and re-used, provided soil is within parameters given below when analysed. Imported topsoil to be good quality sandy loam or manufactured topsoil (from approved source, meeting parameters given below). Topsoil (site-won or imported) is to be tested to determine suitability for proposed use and should be free from commonly tested contaminants, including asbestos; test report to be submitted to Landscape Architect for approval and to enable amelioration recommendations to be made:

Parameter	Unit	Lower Limit	Upper Limit
Clay (<0.002mm)	%	5	18
Silt (0.002-0.05mm)	%	0	35
Sand (0.05-2.0mm) of which at least 40% shall fall into fine to medium sand range	%	50	85
Stones (2-20mm)	% dry wt.	0	20
Stones (20-50mm)	% dry wt.	0	15
Stones (>50mm)	% dry wt.	-	0
pH Value	Unit	5.5	8.5 *
Electrical Conductivity (1:2.5 water extract)	µS/cm	--	1500
Electrical Conductivity (CaSO4 extract)	µS/cm	--	2800
Exchangeable Sodium Percentage	%	--	15
Organic Matter	%	4.0	8.0
Total Nitrogen	%	0.15	--
Carbon: Nitrogen Ratio	--	--	20:1
Extractable Phosphorus	mg/l	26	100
Extractable Potassium	mg/l	240	1200
Extractable Magnesium	mg/l	50	600

*IF AN ACIDIC SITE RANGE SHOULD BE 4.5-6.5 IF ALKALINE 7.5-8.

9. Ameliorant: fertilizer and compost (contractor is responsible for submitting a sample of imported or site-won topsoil (to inform requirements).
Topsoil amelioration to be determined by analysis. Once amelioration requirements ascertained as required, approved (peat free) composts to PAS100 and/or fertilizers to be incorporated during cultivation at required rate to full depth of growing medium.

10. Soil handling and depths.
Management of soils to be in accordance with the Construction Code of Practice for the Sustainable Use of Soils on Construction Sites
i. Topsoil and subsoil to be handled (i.e. excavated and/or imported, stored, spread, cultivated) in accordance with method agreed in writing by Landscape Architect prior to work commencing. All topsoil and subsoil areas shall be thoroughly cultivated by hand or suitable machinery to the full depth of the topsoil layer, incorporating ameliorants as required. If compaction is suspected in sub-grade, subsoil or topsoil surfaces, these should be ripped as necessary to decompact and ensure adequate drainage.
ii. Hand cultivations shall be carried out to achieve the required finish on areas where machine cultivation is impossible ie adjacent to kerbs, manholes and footpath junctions, around retained trees etc. Surplus plant matter, rubbish and surface stones having any dimension greater than 25 mm shall be collected and removed from the site. Topsoil and subsoil is to be stored in heaps, maximum of 2m in height, providing soil is reasonably dry and friable during stripping and handling - using a tracked excavator. To protect from wet weather once final height is achieved, an excavator should regrade the sides and top of stockpile to firm surface by tracking across it to form a smooth gradient.
iii. Final topsoil depth (allowing for settlement) to be 300mm for tree pits and general planting areas and 150mm for grass. Finished soil levels to be 25mm above/below adjoining paving or kerbs: not less than 150mm below dpc of adjoining buildings; shrub areas to be higher than adjoining grass areas by 25 mm. Topsoil to be spread in lightly compacted layers, max. 150mm depth, gently firm each layer before spreading the next.

12. Plant handling and establishment.
Plant handling shall be in accordance with 'Handling and establishing landscape plants', published by the CPSE through the JCLI. (http://www.gohelios.co.uk/nps/handling_establishment.aspx). The contractor shall comply with Part 3: Recommendations for plant handling from delivery to site to ensure successful establishment.

13. General planting notes.
Details for tree, hedge and general planting to be finalised once final site conditions are known (i.e compaction and permeability of ground). General plant stock to conform to BS 3936, advanced nursery stock to BS 8545, and planting to BS 4428. Plants shall be first class examples of their species or variety, free from all pests and diseases, with good fibrous root systems and materially undamaged. All planting operations to be in general compliance with BS4428: 'Code of Practice for general landscape operations'.
Only carry out all planting while soil and weather conditions are suitable:
- Do not plant during periods of frost or strong winds. Plant only during the following periods
- Deciduous and conifer trees: Late October to late March (rootball and bare root)
- Container grown plants: At any time if ground and weather conditions are favourable. Ensure that adequate watering is provided
- Spring-flowering bulbs : September/October

Setting out of planting beds to be approved by Landscape Architect before work commences. Ensure that plant beds are neatly defined, and rise from adjacent paved areas as specified above. All tree pits, tree circles in lawn and planting beds are to be mulched with approved bark mulch to 75mm depth after planting.

14. Tree planting
Any proposed substitutions of species shown on plan to be approved by landscape architect prior to planting. Details for tree planting to comply with BS8545. As a guide all trees to be planted in square pits with base undisturbed unless drainage / compaction problems known. Plant at a depth where the root flare is clearly visible at the soil surface. Where trees have been supplied with the root flare too deep excess soil or fibrous root growth should be removed before planting. All trees to have 'Piddler' tree irrigation/aeration system installed as supplied by Platipus 01737 762300 www.platipus-anchors.com or approved equivalent. Water-in heavily after planting and mulch surface, ensuring mulch is not in contact with trunk of tree. Tree support to comply with BS 8545: Bare root trees to have a single upright stake; RB or CG trees to have double stake and bridge with adjustable tie; tree stakes to be stained black. Any necessary remedial tree works are to be carried out by an approved tree surgeon to BS 3998. Trees planted within grass areas to be set in mulched earth circles, 1m diameter around tree trunk, with turf trimmed neatly to form circle. Fruit trees in community orchard to be durably labeled with name of variety.
i. Trees up to 20cm girth.
Depth of tree pits to be the same as the rootball and with overall width to be 150mm wider than the diameter of the rootball (75mm min. from rootball edge to tree pit side). Pits to be backfilled with 300mm depth of specified topsoil over subsoil as per spec.

15. Hedges.
Depth of planting trench to be same as rootball, overall width150mm wider than rootball (75mm min. from rootball edge to sides of trench). Trench to be backfilled with 300mm depth of specified topsoil over subsoil as per spec. Fertiliser to be incorporated as required to ensure establishment and continued thriving of plants - type and application rate to be determined by analysis. Central post and wire supporting to be provided with two line wires and plants to be tied in using horticultural plastic ties. On planting, hedges to be trimmed to 900mm ht. and sides trimmed to neat shape where necessary.

16. Native hedges.
Species to be randomly mixed for natural effect, and planted in groups of 3-5 plants of any one species. Depth of planting trench to be same as root system, overall width space 150mm wider than root system (75mm min. from root system edge to sides of trench). Trench to be backfilled with 300mm depth of specified topsoil over subsoil as per spec. Provide and install each plant with an appropriate sized recyclable staked green shrub shelter (available from Tubex Ltd, phone 01621 874201 or similar approved). Position shelter stake on windward side of plant, drive vertically into bottom of pit before planting, to a min. depth of 300mm and consolidate backfill material around stake; attach shelter to stake with a minimum of two ties.

17. Native tree and shrub mix.
All plants to be planted in cultivated planting beds with species randomly mixed for natural effect, and planted in groups of 3-5 plants of any one species. Plants to be notch- or pit-planted. Plant on grid at spacing given in schedule. Provide and install each plant with an appropriate sized recyclable staked green tree or shrub shelter (available from Tubex Ltd phone 01621 874201 or similar approved). Position shelter stake on windward side of plant, drive vertically into bottom of pit before planting, to a min. depth of 300mm and consolidate backfill material around stake; attach shelter to stake with a minimum of two ties.

18. Shrub and Ground Cover Planting.
All plants to be planted into cultivated planting beds (with 300mm depth specified topsoil) at densities shown in plant schedule, backfilled with same topsoil. Fertiliser to be incorporated as required to ensure establishment and continued thriving of plants - type and application rate to be determined by analysis.

19. Climbers.
All climbers to be planted as 19. above and provided with steel line wires attached to the wall/fence/trellis (min 3 no.) at 300mm vertical spacing with climbers spread out and tied to wires using appropriate horticultural ties. Fertiliser to be incorporated as required to ensure establishment and continued thriving of plants - type and application rate to be determined by analysis.

20. Bulb planting.
All bulbs to be planted at the rate given in the schedule, in random mixed drifts of single species in areas indicated on the plan, minimum 15 bulbs per drift of single species. For planting, naturalize bulb positions by dropping bulbs from waist height. Neatly remove a plug of turf and replace after planting. Plant so that the top of the bulb is at a depth of approximately twice its height with base in contact with bottom of hole. Bulbs should be no closer together than approximately twice the width of a single bulb.

21. Grass.
Turfing and seeding shall be carried out only during appropriate seasons and while soil and weather conditions are suitable for the relevant operations. Only machinery and tools suitable for the site conditions and the work to be carried out shall be used. Hand tools shall be used around trees, plants and in confined spaces where it is impractical to use machinery. The soil shall be weed free prior to turfing and seeding. Contact herbicide as specified should be applied to all areas of weed growth 4-6 weeks before grassing and repeated if necessary to maintain a weed free bed. Where deep rooted weeds are present (docks, thistles etc.) approved Glyphosate-based herbicide should be applied as a spot treatment. Turf or seed shall be laid on prepared, levelled soil (minimum 150mm depth) in the areas indicated on the drawings in accordance with BS 4428:1989 'Code of practice for general landscape operations'. All grass areas to be approved landscape quality turf for general amenity areas or lawn turf for garden areas, or equivalent seed.

22. Wildflower meadows.
Establish seed mix & soil requirements from supplier.

23. Maintenance.
Establishment maintenance for all planting for 5 years from Practical Completion to include weed control, watering and replacement of failures to original specification in the planting season following failure.
i. All plant material to receive annual species-specific pruning and hedges and groundcover to be trained and edged with minimum 2 trims per year.
ii. Check tree stakes and ties annually and after strong winds.
iii. All fruit trees within community orchard to receive appropriate annual pruning to promote fruiting in line with supplier's recommendations.
iv. Check shrub shelters at least twice annually to remove weeds and any soil build up inside tube. Shelters to be removed in year 3 and recycled.
v. Native shrubs plants to be trimmed during winter just after planting, then twice annually in summer and autumn to encourage lower branching and dense growth.
vi. Lawn & amenity grass areas - Mowing is to be carried out using approved machinery to maintain the vegetation length within the limits of 30 mm and 50 mm during April to August inclusive and between 50 mm and 70 mm during the rest of the year.
A. Wildflower meadows. Follow suppliers recommendations

rev.	date	by	chk	notes
P10	06.08.19	AS	-	Changes to plan following revised layout
P09	27.05.19	AS	-	Proposed trees coordinated with drainage proposals
P08	22.05.19	AS	-	Minor revision to landscape materials
P07	21.05.19	DP	AS	Changes to plan following revised layout
P06	12.04.19	DP	-	Adjustments to planting layout following comments
P05	12.04.19	DP	AS	Changes to plan following revised layout
P04	11.01.19	AS	-	Entrance road revised to reflect changes
P03	10.01.19	DP	AS	Pubic open space revised
P02	21.12.18	AS	-	Revised planning issue
P01	20.12.18	KB	AS	Planning issue

project	Cinders Nursery, Yapton		
title	Landscape Proposals		
status	Planning	scale @ A1	1:500
dwg no	1973-TF-00-00-DR-L-1001		
references	19.14.P101 Q rev. I, by Crayfern Homes dated 11.04.2019		

terrafirma
LANDSCAPE ARCHITECTS

Suite B, Ideal House, Bedford Road, Petersfield, Hampshire GU32 3QA
Tel: +44 (0)1730 262 040
Web: www.terrafirmaconsultancy.com

© Copyright reserved 2019

ARUN DISTRICT COUNCIL Y/14/19/RES