



PHILIPS SURVEYORS

**Longacre,
Maypole Lane, Yapton, West Sussex**

Detailed Plant Schedule and Specification

Planning Issue

Prepared by	SL
Checked by	
Date	28 th February 2017
Document Reference	LLD1129_R05
Revision	01

DETAILED PLANT SCHEDULE

Ornamental Species Tree Planting				
Name	Size	Pot	Density	Number
<i>Amelanchier arborea</i> 'Robin Hill' (Cherry)	14 – 16 cm Girth Size; 4.25 – 6.0 m height; Standard (Extra Heavy).	85 ltr CG	As Shown	3
<i>Prunus 'Pandora'</i> (Cherry)	14 – 16 cm Girth Size; 4.25 – 6.0 m height; Standard (Extra Heavy).	65 /85 ltr CG	As Shown	1
<i>Sorbus intermedia</i> (Swedish Whitebeam)	14 – 16 cm Girth Size; 4.25 – 6.0 m height; Standard (Extra Heavy).	85 ltr CG	As Shown	1

Native Species Tree Planting				
Name	Size	Pot	Density	Number
<i>Acer campestre</i> (Field Maple)	12 – 14 cm Girth Size; 3.5 – 4.25 m height; Standard (Heavy).	45 / 65 ltr CG	Specimen	2
<i>Malus sylvestris</i> (Crab Apple)	12 – 14 cm Girth Size; 3.5 – 4.25 m height; Standard (Heavy).	45 ltr CG	Specimen	2
<i>Quercus robur</i> (Pedunculate Oak)	12 – 14 cm Girth Size; 3.5 – 4.25 m height; Standard (Heavy).	45 ltr CG	Specimen	1
<i>Sorbus aucuparia</i> (Rowan)	12 – 14 cm Girth Size; 3.5 – 4.25 m height; Standard (Heavy).	45 ltr CG	Specimen	2
<i>Sorbus torminalis</i> (Wild Service Tree)	12 – 14 cm Girth Size; 3.5 – 4.25 m height; Standard (Heavy).	45 ltr CG	Specimen	1

CG – Container Grown Stock; RB – Root Balled Stock; BR – Bare Root Stock.

PHILIPS SURVEYORS

Longacre,
Maypole Lane, Yapton, West Sussex
LLD1129/R05.Rev01/SL/February 2017

Native Mixed-Species Boundary Hedge Planting (Plant in random groups of 3-5-7-s)				
Name	Size	Pot	Percentage	Number
<i>Carpinus betulus</i> (Hornbeam)	80 – 100 cm height; Multi-Branched.	BR	20%	99
<i>Cornus sanguinea</i> (Dogwood)	80 – 100 cm height; Multi-Branched.	BR	20%	99
<i>Crataegus monogyna</i> (Hawthorn)	80 – 100 cm height; Multi-Branched.	BR	20%	99
<i>Ilex aquifolium</i> (Holly)	60 – 80 cm height; Multi-Branched.	CG	20%	99
<i>Rosa canina</i> (Dog Rose)	60 – 80 cm height; Transplant.	BR	20%	99

(Native boundary hedge planting to be 2 no. staggered rows set 400 mm apart @ 400mm centres).

Ornamental Single-Species Boundary & Frontage Hedge Planting				
Name	Size	Pot	Density	Number
<i>Griselinia littoralis</i>	60 – 80 cm height; Instant Hedging	CG	--	84 m
<i>Eleagnus x ebbingei</i> 'Oleaster'	60 – 90 cm height. Multi-Branched.	5 ltr CG	3 p/m	120

(Ornamental instant frontage hedge planting to be 1.0 metre length troughs laid in a single row; and ornamental boundary hedge planting to be single row, 3 plant / linear meter).

BR – Bare Rooted Stock; CG – Container Grown Stock.

PHILIPS SURVEYORS

Longacre,
Maypole Lane, Yapton, West Sussex
LLD1129/R05.Rev01/SL/February 2017

Specimen Planting				
Name	Size	Pot	Density	Number
<i>Choisya</i> 'Aztec Pearl'	40 – 60 cm height; Bushy.	15 ltr CG	Specimen	1
<i>Cornus alba</i> 'Ivory Halo'	60 – 80 cm height; Multi-Branched.	15 ltr CG	Specimen	1
<i>Deutzia x</i> 'Mont Rose'	60 – 80 cm height; Branched.	15 ltr CG	Specimen	3
<i>Philadelphus</i> 'Belle Etoile'	60 – 80 cm spread; Bushy.	15 ltr CG	Specimen	1

CG – Container Grown Stock;

Flowering Shrub & Ground Cover Planting				
Name	Size	Pot	Density	Number
<i>Brachyglottis</i> 'Sunshine'	30 – 40 cm height; Branched.	3 ltr CG	3 / m ²	23
<i>Carex</i> 'Silver Sceptre'	30 – 40 cm spread; Full Pot.	3 ltr CG	3 / m ²	6
<i>Cistus x purpureus</i>	30 – 40 cm height; Bushy.	3 ltr CG	3 / m ²	16
<i>Cornus stolonifera</i> 'Flaviramea'	30 – 40 cm height; Bushy.	3 ltr CG	3 / m ²	8
<i>Euonymus fortunei</i> 'Emerald Gaiety'	20 – 30 cm height; Bushy.	3 ltr CG	5 / m ²	20
<i>Hebe brachysiphon</i> 'White Gem'	30 – 40 cm height; Bushy.	3 ltr CG	5 / m ²	16
<i>Lavandula angustifolia</i> 'Munstead'	20 – 30 cm height; Bushy.	3 ltr CG	3 / m ²	9
<i>Liriope muscari</i>	Full Pot	3 ltr CG	5 / m ²	20
<i>Pachisandra terminalis</i> 'Green Carpet'	20 – 30 cm height; Bushy.	3 ltr CG	3 / m ²	26
<i>Spiraea japonica</i> 'Little Princess'	30 – 40 cm height; Bushy.	3 ltr CG	4 / m ²	8

CG – Container Grown Stock;

PHILIPS SURVEYORS

Longacre,
Maypole Lane, Yapton, West Sussex
LLD1129/R05.Rev01/SL/February 2017

Accent & Herbaceous Planting				
Name	Size	Pot	Density	Number
<i>Anemanthele lessoniana</i>	30 cm spread; Full Pot.	2 ltr CG	Specimen	3
<i>Bergenia cordifolia</i> 'Purpurea'	30 cm spread; Full Pot.	2 ltr CG	Specimen	9
<i>Centranthus ruber</i> var. 'Coccineus'	30 cm spread; Full Pot.	2 ltr CG	Specimen	6
<i>Epimedium x youngianum</i> 'Niveum'	30 cm spread; Full Pot.	3 ltr CG	Specimen	3
<i>Hakonechloa macra</i> 'Aureola'	30 cm spread; Full Pot.	3 ltr CG	Specimen	5
<i>Miscanthus sinensis</i> 'Gracillimus'	30 – 40 cm spread; Full Pot.	7 ltr CG	Specimen	3
<i>Molinia caerulea</i> 'Variegata'	30 - 40 cm spread; Full Pot.	7 ltr CG	Specimen	6

CG – Container Grown Stock;

Meadow Grassland and Wildflower Seed Mix

- Area of wildflower grassland is proposed to the northern edge of the internal development access road.

Meadow Grassland and Wildflower Seed Mix	
<i>Emorsgate's EM1 Basic General Purpose Meadow Mixture</i> <i>or equal and approved</i>	82 m ²

Wildflower grassland areas to be seeded with Emorsgate – EM1: Basic General Purpose Meadow Mixture; Wildflower grassland areas to be seeded over bare ground.

Sowing Rate = 4g / m².

PHILIPS SURVEYORS

Longacre,
Maypole Lane, Yapton, West Sussex
LLD1129/R05.Rev01/SL/February 2017