

WOODLANDS PARK

Proposed brick/concrete block boundary wall.
(Part retrospective)

Height: 2m.

Thickness: 210mm (103mm brick to face externally to Canal Road, 100mm concrete block to face internally to Woodlands Park).

Length: 57.5m

Piers every 3m.

Foundations: 0.5m deep, 600mm wide with 150mm concrete footing.

Brick: Freshfield Lane First Quality Facings.

Capping: Warnham Red Stock.

Block: Thakeham Calxite General Purpose Concrete Block
100m

(To match existing wall, planning permission Y/33/12).