




From: Laura Gibbons <Laura.Gibbons@arun.gov.uk>

Sent: 15 September 2020 09:52

To: Planning.Responses <Planning.Responses@arun.gov.uk>

Cc: Simon Davis <Simon.Davis@arun.gov.uk>

Subject: Y/70/20/OUT- Land East of Bilsham Road & Land Adjacent to Little Meadow Bilsham Road Yapton

Engineers Comments Regarding Surface Water Drainage

A drainage strategy has been submitted indicating that the hierarchy for sustainable drainage will be followed with infiltration fully investigated. Winter infiltration testing and winter groundwater monitoring must be undertaken, it is advised that the applicant discusses the extent of this monitoring with us at the earliest opportunity. Infiltration tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location.

If on-site infiltration is not possible, drainage via a restricted discharge to a suitable local watercourse may be acceptable. Any discharge should be restricted to QBAR greenfield run-off rates, with a minimum rate of 2l/s. This is in accordance with the drainage strategy submitted, where preliminary means of surface water disposal have been given, including discharge rates and preliminary storage calculations for each of the development areas.

We note that there is an ordinary watercourse to the east of the development area, a minimum of a 3m wide buffer must be provided between the top of bank of watercourse and any structures that would limit access. It is noted that it is proposed that a connection may be made to the pond, we would request that further investigation of the pond and its connections is completed if such a connection is found to be required. Peak pond water levels must be provided, we will not permit discharge to this pond unless we are confident that the pond can adequately cope with such flows (i.e. it is proven that it discharges to ground or other source).

The flood risk assessment submitted suggests that localised land raising to the south of the development will be required to bring proposed homes out of future flood zone 3a. This would be supported if it is demonstrated that this will not have a knock on negative impact upon surface water drainage. Pumping is not a sustainable solution and will not be accepted, natural topography should be followed. To support the next stage of design we request that topographic survey is completed and catchment areas are properly delineated based upon this. These catchments should then be followed in the wider layout design and surface water drainage solution.

We suggest that, at the earliest stage, the developer gives due consideration to the appropriate location and design of surface water drainage features to achieve necessary capacity, water quality (via the SuDS management/treatment train), as well as ease of on-going maintenance. Surface water drainage features should also be designed in a manner that positively affects the amenity of the site. We would like to remind the developer that, open features, such as swales, basins and ponds, when designed correctly, can satisfy all the above aspirations in addition to; being easier to maintain, having longer lifespans and offering ecological advantages over subterranean features such as “plastic crate systems”.

It should also be noted that attenuation features should not be counted within useable public open space provision.

If you are minded to approve this application we request that the following conditions are applied:

PCENG D2- Given the complexities of the site we would request our standard condition is adjusted as below (or similar) to be at or before reserved matters stage, rather than pre-commencement.

“Full details of the proposed surface water drainage scheme shall be submitted and approved in writing by the Local Planning Authority at or before reserved matters stage. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORM D

“Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers.

Supplementary guidance notes regarding surface water drainage are located here

<https://www.arun.gov.uk/surfacewater> on Arun District Councils website. A surface water drainage checklist is available on Arun District Councils website, this should be submitted with a Discharge of Conditions Application.”

PCENG D3

“The development shall not proceed until details have been submitted to and approved in writing by the Local Planning Authority for any proposals: to discharge flows to watercourses; or for the culverting, diversion, infilling or obstruction of any watercourse on or adjacent to the site. Any discharge to a watercourse must be at a rate no

greater than the pre-development run-off values. No construction is permitted, which will restrict current and future land owners from undertaking their riparian maintenance responsibilities in respect to any watercourse or culvert on or adjacent to the site. “

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W DM1, W DM2 and W DM3 of the Arun Local Plan. And to ensure that the duties and responsibilities, as required under the Land Drainage Act 1991, and amended by the Flood and Water Management Act 2010, can be fulfilled without additional impediment following the development completion. It is considered necessary for this to be a pre-commencement condition to protect existing watercourses prior to the construction commencing.

And the accompanying informative:

INFORMD2

“Under Section 23 of the Land Drainage Act 1991 Land Drainage Consent must be sought from the Lead Local Flood Authority (West Sussex County Council), or its agent (Arun District Council land.drainage@arun.gov.uk), prior to starting any works (temporary or permanent) that affect the flow of water in an ordinary watercourse. Such works may include culverting, channel diversion, discharge of flows, connections, headwalls and the installation of trash screens.

The development layout must take account of any existing watercourses (open or culverted) to ensure that future access for maintenance is not restricted. No development is permitted within 3m of the bank of an ordinary watercourse, or 3m of a culverted ordinary watercourse.”

PCENG4

“Development shall not commence until full details of the maintenance and management of the surface water drainage system is set out in a site-specific maintenance manual and submitted to, and approved in writing, by the Local Planning Authority. The manual is to include details of financial management and arrangements for the replacement of major components at the end of the manufacturer's recommended design life. Upon completed construction of the surface water drainage system, the owner or management company shall strictly adhere to and implement the recommendations contained within the manual.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W DM1, W DM2 and W DM3 of the Arun Local Plan. It is considered necessary for this to be a pre-commencement condition to ensure that the future maintenance and funding arrangements for the surface water disposal scheme are agreed before construction commences.

ENG1

“Immediately following implementation of the approved surface water drainage system and prior to occupation of any part of the development, the developer/applicant shall provide the local planning authority with as-built drawings of the implemented scheme together with a completion report prepared by an independent engineer that confirms that the scheme was built in accordance with the approved drawing/s and is fit for purpose. The scheme shall thereafter be maintained in perpetuity.”

Reason : To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan.

Regards,

Laura Gibbons

Drainage Engineer

Engineering Services

Please note that I work Tuesdays 08:00-16:00 for Arun only.



T: 01903 221374

E: laura.gibbons@arun.gov.uk or



Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF