

- ## RESIDUAL HAZARDS

1. Uncharted buried services. Contractor to use CAT prior to excavating.
2. Working in live carriageway. Contractor to implement traffic management to ensure safety of the workforce and public.
3. Working in live sewers. Contractor to ensure operatives are familiar with the dangers of working in live sewers.
4. Excavations close to existing structures. Contractor to prepare method statement to ensure stability of existing structures.

All adoptable drainage works to be constructed as detailed in the Code for Adoption Design and Construction Guidance.



Drawing Status **FOR APPROVAL**

Project **BILSHAM ROAD
YAPTON**

Scale NTS	Date FEB 22	Drawn By	Checked By
--------------	----------------	----------	------------

FIGURE B5
TYPICAL MANHOLE DETAIL - TYPE A1
Depth from cover level to pipe soffit 3.0 - 6.0m
Rigid material construction with concrete surround

