



Local Policing Support Team

Your Ref: Y/71/20/RES

Our Ref: LM/ARU/20/22A

Date 26th August 2020

Contact Name: Lee Melbourne

Dear Mr Davies,

RE: Land North of Yapton Church of England Primary School North End Road Yapton

Thank you for your correspondence of the 20th August 2020, advising me of a planning application for Approval of reserved matters following outline consent Y/88/18/OUT for the erection of 38 No. dwellings. This application affects Public Rights of Way at the above location, for which you seek advice from a crime prevention viewpoint.

I have had the opportunity to examine the detail within the application and in an attempt to reduce the opportunity for crime and the fear of crime I offer the following comments from a Secured by Design (SBD) perspective. SBD is owned by the UK Police service and supported by the Home Office and Building Control Departments in England (Part Q Security – Dwellings), that recommends a minimum standard of security using proven, tested and accredited products. Further details can be found at www.securedbydesign.com

The National Planning Policy Framework demonstrates the government's aim to achieve healthy, inclusive and safe places which are safe and accessible, so that crime and disorder, and the fear of crime, do not undermine the quality of life or community cohesion. With the level of crime and anti-social behaviour in the Arun District being average when compared with the rest of Sussex, I have no major concerns with the proposals, however, additional measures to mitigate against any identified local crime trends and site specific requirements should always be considered.

I refer the applicant to previous correspondence from this office Your Ref: Y/88/18/OUT dated the 20th November 2018 and Our Ref: NW/ARU/18/17A dated the 7th December 2018 to which all comments remain extant.

Mr Davies
Planning Officer
Planning Control
Arun District Council

Sussex Police Headquarters
Malling House, Malling, Lewes, East Sussex, BN7 2DZ

I direct the applicant or their agent to our website at www.securedbydesign.com where the SBD Homes 2019 Version 2 document can be found. The Secured by Design scheme is a Police initiative to guide and encourage those engaged within the specification, design and build of new homes, and those undertaking major or minor property refurbishment, to adopt crime prevention measures. The advice given in this guide has been proven to reduce the opportunity for crime and the fear of crime, creating safer, more secure and sustainable environments.

With regards to the layout the development in the main has outward facing dwellings with back to back gardens which has created good active frontage with the streets and the public areas being overlooked, this design has all but eliminated the need for vulnerable rear garden pathways.

With regards to the communal parking areas it is important that these are within view of an active room within the property. An active room is where there is direct and visual connection between the room and the street or the car parking area. Such visual connections can be expected from rooms such as kitchens and living rooms, but not from bedrooms and bathrooms.

With regards to the LAP - areas of play should be situated in an environment that is stimulating and safe for all children, be overlooked with good natural surveillance to ensure the safety of users and the protection of equipment, which can be vulnerable to misuse. They should be designed to allow natural surveillance from nearby dwellings with safe and accessible routes for users to come and go. Boundaries between public and private space should be clearly defined and open spaces must have features which prevent unauthorised vehicular access. This will be of particular pertinence to this application as the design and access statement states that the majority of visitor parking will be allocated close to this area.

I would ask that when consideration is given to the eventual location that it is surrounded with railings with self-closing gates to provide a dog free environment.

With regards to the proposed landscaping and planting from a crime prevention perspective I ask that ground planting should not be higher than 1 metre with tree canopies no lower than 2 metres. This arrangement provides a window of observation throughout the area.

With regards to the footpaths sited throughout the development SBD states that:

Public footpaths should not run to the rear of, and provide access to gardens, rear yards or dwellings as these have been proven to generate crime. Where a segregated footpath is unavoidable, for example a public right of way, an ancient field path or heritage route, designers should consider making the footpath a focus of the development and ensure that they are as straight as possible • wide • well lit (within BS 5489-1:2013) • devoid of potential hiding places • overlooked by surrounding buildings and activities • well maintained so as to enable natural surveillance along the path and its borders. For further information on footpath design I direct the applicant to SBD Homes Version 2 2019 Chapter 8 see paragraphs 8.8 – 8.12.

Thank you for giving me an opportunity to comment.

Sussex Police Headquarters
Malling House, Malling, Lewes, East Sussex,
BN7 2DZ



The Crime & Disorder Act 1998 heightens the importance of taking crime prevention into account when planning decisions are made. Section 17 of the Act places a clear duty on both police and local authorities to exercise their various functions with due regard to the likely effect on the prevention of crime and disorder. You are asked to accord due weight to the advice offered in this letter which would demonstrate your authority's commitment to work in partnership and comply with the spirit of The Crime & Disorder Act.

Yours sincerely



Miss Lee A Melbourne
Designing Out Crime Officer
Sussex Police Headquarters

Sussex Police Headquarters
Malling House, Malling, Lewes, East Sussex,
BN7 2DZ

