



Odyssey, Burndell Road, Yapton
1.6m Precast Concrete Storm Water Attenuation Tank
- Preliminary Floatation Check
Project No: STS2477

Calculations By:	E. Wajs
Checked By:	P. Lyons
Date:	6 th August 2019

Revision:	Date:	Comment:
0	06.08.2019	Issued for Comment

Reference Documents:

IS EN 1990	Eurocode - Basis of Structural Design
IS EN 1997-1	Eurocode 7 - Geotechnical Design – General Rules

Design Assumptions:

Assumed Internal Water Level:	Assumed Empty for Floatation Check
Assumed Overburden Depth:	0.55m
Soil Bulk Density:	20 kN/m ³
Density of Groundwater:	9.81 kN/m ³
Assumed Concrete Density:	24 kN/m ³ (Mass Concrete) 14 kN/m ³ (Buoyant)
Assumed Ground Water Level:	1.0m below surface
Tank External Height:	2.075m

Tank Plan Area:	=	154.0 m ²
-----------------	---	----------------------

Self Weight of Tank:

External Walls (51.7t):	51.7 x 9.81	=	507.2 kN
Internal Walls (16.5t):	16.5 x 9.81	=	161.9 kN
Dry Flow Channels (3.0t)	3.0 x 9.81	=	29.4 kN
Precast Roof Slabs (47.0t):	47.0 x 9.81	=	461.1 kN
Insitu Base Slab (34.0m ³):	34 x 25.0	=	850.0 kN
Insitu Wall Joints (3.2m ³):	3.2 x 25.0	=	80.0 kN
Insitu Roof Screed (19.7m ³):	19.7 x 25.0	=	<u>492.5</u> kN
			2582.1 kN

Factored Resistance to Uplift:	0.9 x 2582.1	=	2323.9 kN
--------------------------------	--------------	---	-----------

Weight of overburden (550mm):	154 x 0.55 x 20	=	1694.0 kN
-------------------------------	-----------------	---	-----------

Factored Resistance to Uplift:	0.9 x 1694	=	1524.6 kN
--------------------------------	------------	---	-----------

Total Resistance to Uplift Factored:	2323.9 + 1524.9	=	4017.9 kN
--------------------------------------	-----------------	---	-----------

Submerged Depth of Tank:	0.55 + 2.075 – 1.0	=	1.625m
--------------------------	--------------------	---	--------

Factored Uplift:	1.1 x 154.0 x 9.81 x 1.625	=	2700.4 kN < 4017.9 kN - ok
------------------	----------------------------	---	----------------------------

Localised Structural Uplift Check

Self Weight of Tank:

Roof Slab:	0.250×25.0	=	6.3 kN/m^2
S/W Internal Walls	$(1.5 \times 9.81) / (3.3 \times 2.4)$	=	1.9 kN/m^2
Inistu Base Slab:	0.225×25.0	=	$\frac{5.6 \text{ kN/m}^2}{13.8 \text{ kN/m}^2}$

Weight of overburden (550mm):	0.55×20	=	11.0 kN/m^2
-------------------------------	------------------	---	-----------------------

Total Resistance to Uplift:	$13.8 + 11.0$	=	24.8 kN/m^2
-----------------------------	---------------	---	-----------------------

Submerged Depth of Tank:	$0.55 + 2.075 - 1.0$	=	1.625m
--------------------------	----------------------	---	-----------------

Factored Uplift:	$1.1 \times 9.81 \times 1.625$	=	$17.5 \text{ kN/m}^2 < 24.8 \text{ kN/m}^2 - \text{ok}$
------------------	--------------------------------	---	---