GENERIC SAP CALCULATIONS FOR YAPTON INCLUDING PV CALCULATIONS

Dwelling	Reference	Built Form	Orientation	SAP	DER	TER	Percent Improvement	Total Floor Area	Air permeability	PV Energy Produced (DER)	Total CO2 (DER)	Total CO2 (TER)	Boiler Make	Boiler Model	Model Qual	Ventilation Type	PV Kwp	PV Orientation
Plot 34 T4	T4	Mid-terrace	South West	B 84 (83.8687456533521)	17.4	18.15	4.13	78.98	5	0	1374.44	1433.55	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 44 T4	T4	Mid-terrace	North East	B 84 (84.0624415732949)	17.01	17.79	4.38	78.98	5	0	1343.82	1405.37	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 41 T4	T4	Mid-terrace	North East	B 84 (84.0624415732949)	17.01	17.79	4.38	78.98	5	0	1343.82	1405.37	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 17 T4	T4	End-terrace	North West	B 84 (83.8428133725584)	17.29	18	3.94	78.98	5	0	1365.68	1421.49	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 16 T4	T4	End-terrace	North West	B 84 (83.8428133725584)	17.29	18	3.94	78.98	5	0	1365.68	1421.49	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 102 T4	T4	End-terrace	North West	B 84 (83.8428133725584)	17.29	18	3.94	78.98	5	0	1365.68	1421.49	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 101 T4	T4	End-terrace	North West	B 84 (83.8428133725584)	17.29	18	3.94	78.98	5	0	1365.68	1421.49	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 28 T4	T4	End-terrace	South East	B 84 (83.8082448308832)	17.36	18.07	3.93	78.98	5	0	1371.13	1426.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 29 T4	T4	End-terrace	South East	B 84 (83.8082448308832)	17.36	18.07	3.93	78.98	5	0	1371.13	1426.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 33 T4	T4	End-terrace	South West	B 84 (83.6632017527884)	17.65	18.35	3.81	78.98	5	0	1393.91	1449.05	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 35 T4	T4	End-terrace	South West	B 84 (83.6632017527884)	17.65	18.35	3.81	78.98	5	0	1393.91	1449.05	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 38 T4	T4	End-terrace	North East	B 91 (91.491726058259)	9.1	17.72	48.65	78.98	5	-1204.8	718.42	1399.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	1.5	SW REAR
Plot 39 T4	T4	End-terrace	North East	B 91 (91.491726058259)	9.1	17.72	48.65	78.98	5	-1204.8	718.42	1399.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	1.5	SW REAR
Plot 40 T4	T4	End-terrace	North East	B 84 (83.9818989231662)	17.01	17.72	4.01	78.98	5	0	1343.71	1399.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 42 T4	T4	End-terrace	North East	B 84 (83.9818989231662)	17.01	17.72	4.01	78.98	5	0	1343.71	1399.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 43 T4	T4	End-terrace	North East	B 84 (83.9818989231662)	17.01	17.72	4.01	78.98	5	0	1343.71	1399.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 45 T4	T4	End-terrace	North East	B 84 (83.9818989231662)	17.01	17.72	4.01	78.98	5	0	1343.71	1399.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 2 T5	T5	Semi-detached	South West	B 84 (84.0820530845483)	16.95	17.57	3.53	86.7	5	0	1469.27	1523.28	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 3 T5	T5	Semi-detached	South West	B 84 (84.0820530845483)	16.95	17.57	3.53	86.7	5	0	1469.27	1523.28	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 8 T5	T5	Semi-detached	South West	B 84 (84.0820530845483)	16.95	17.57	3.53	86.7	5	0	1469.27	1523.28	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 9 T5	T5	Semi-detached	South West	B 84 (84.0820530845483)	16.95	17.57	3.53	86.7	5	0	1469.27	1523.28	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 10 T5	T5	Semi-detached	South West	B 84 (84.0820530845483)	16.95	17.57	3.53	86.7	5	0	1469.27	1523.28	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 11 T5	T5	Semi-detached	South West	B 84 (84.0820530845483)	16.95	17.57	3.53	86.7	5	0	1469.27	1523.28	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 20 T5	T5	Semi-detached	South East	B 84 (84.175251763542)	16.77	17.4	3.62	86.7	5	0	1453.79	1508.27	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 52 T5	T5	Semi-detached	North West	B 84 (84.1824321210459)	16.75	17.38	3.62	86.7	5	0	1452.6	1507.11	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 55 T5	T5	Semi-detached	South East	B 84 (84.175251763542)	16.77	17.4	3.62	86.7	5	0	1453.79	1508.27	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 75 T5	T5	Semi-detached	North West	B 91 (91.2520480283622)	9.54	17.38	45.11	86.7	5	-1204.8	827.31	1507.11	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	1.5	SE REAR
Plot 80 T5	T5	Semi-detached	South East	B 84 (84.175251763542)	16.77	17.4	3.62	86.7	5	0	1453.79	1508.27	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 88 T5	T5	Semi-detached	South East	B 84 (84.175251763542)	16.77	17.4	3.62	86.7	5	0	1453.79	1508.27	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 100 T5	T5	Semi-detached	North West	B 91 (91.2520480283622)	9.54	17.38	45.11	86.7	5	-1204.8	827.31	1507.11	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	1.5	SE REAR
Plot 108 T7	T7	Detached	North East	A 92 (92.1716258599074)	9.22	17.64	47.73	102.9	5	-1606.39	948.58	1814.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SW REAR
Plot 79 T7	T7	Detached	North East	A 92 (92.1716258599074)	9.22	17.64	47.73	102.9	5	-1606.39	948.58	1814.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SW REAR
Plot 76 T7	T7	Detached	North East	A 92 (92.1716258599074)	9.22	17.64	47.73	102.9	5	-1606.39	948.58	1814.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SW REAR
Plot 78 T7	T7	Detached	North East	B 84 (83.7779514254254)	17.32	17.64	1.81	102.9	5	0	1782.3	1814.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 77 T7	T7	Detached	North East	B 84 (83.7779514254254)	17.32	17.64	1.81	102.9	5	0	1782.3	1814.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 54 T7	T7	Detached	North East	A 92 (92.1716258599074)	9.22	17.64	47.73	102.9	5	-1606.39	948.58	1814.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SW REAR
Plot 53 T7	T7	Detached	North East	B 84 (83.7779514254254)	17.32	17.64	1.81	102.9	5	0	1782.3	1814.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 19 T7	T7	Detached	North East	B 84 (83.7779514254254)	17.32	17.64	1.81	102.9	5	0	1782.3	1814.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 1 T7	T7	Detached	North West	A 92 (92.0578816513086)	9.42	17.81	47.11	102.9	5	-1606.39	969.04	1833.07	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SE REAR
Plot 89 T7	T7	Detached	South East	B 84 (83.7575868596192)	17.36	17.67	1.75	102.9	5	0	1785.97	1818.16	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 99 T7	T7	Detached	South West	B 84 (83.643420634974)	17.56	17.85	1.62	102.9	5	0	1806.49	1836.36	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 13 T9	T9	Semi-detached	South West	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 12 T9	T9	Semi-detached	South West	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 7 T9	T9	Semi-detached	South West	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 6 T9	T9	Semi-detached	South West	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 21 T9	T9	Semi-detached	South East	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 22 T9	T9	Semi-detached	South East	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 23 T9	T9	Semi-detached	South East	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 24 T9	T9	Semi-detached	South East	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 83 T9	T9	Semi-detached	South East	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 84 T9	T9	Semi-detached	South East	B 85 (85.3010512568417)	15.03	15.73	4.45	109.74	5	0	1649.47	1726.51	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 48 T9	T9	Semi-detached	North West	B 85 (85.3605260862021)	14.92	15.62	4.48	109.74	5	0	1637.82	1714.48	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 49 T9	T9	Semi-detached	North West	B 85 (85.3605260862021)	14.92	15.62	4.48	109.74	5	0	1637.82	1714.48	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 50 T9	T9	Semi-detached	North West	B 85 (85.3605260862021)	14.92	15.62	4.48	109.74	5	0	1637.82	1714.48	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 51 T9	T9	Semi-detached	North West	B 85 (85.3605260862021)	14.92	15.62	4.48	109.74	5	0	1637.82	1714.48	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 14 T12	T12	Detached	South West	B 84 (84.1636790061987)	16.78	17.03	1.47	113.3	5	0	1901.67	1929.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 31 T12	T12	Detached	South West	B 84 (84.1636790061987)	16.78	17.03	1.47	113.3	5	0	1901.67	1929.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 32 T12	T12	Detached	South West	B 84 (84.1636790061987)	16.78	17.03	1.47	113.3	5	0	1901.67	1929.83	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 18 T12	T12	Detached	North West	A 92 (92.079273713284)	9.3	16.91	45	113.3	5	-1606.39	1053.86	1915.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SE REAR
Plot 46 T12	T12	Detached	North West	A 92 (92.079273713284)	9.3	16.91	45	113.3	5	-1606.39	1053.86	1915.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SE REAR
Plot 105 T12	T12	Detached	North West	A 92 (92.079273713284)	9.3	16.91	45	113.3	5	-1606.39	1053.86	1915.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SE REAR
Plot 107 T12	T12	Detached	North West	A 92 (92.079273713284)	9.3	16.91	45	113.3	5	-1606.39	1053.86	1915.9	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SE REAR
Plot 25 T12	T12	Detached	South East	B 84 (84.2713636320421)	16.6	16.85	1.48	113.3	5	0	1880.98	1909.37	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 27 T12	T12	Detached	South East	B 84 (84.2713636320421)	16.6	16.85	1.48	113.3	5	0	1880.98	1909.37	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 30 T12	T12	Detached	South East	B 84 (84.2713636320421)	16.6	16.85	1.48	113.3	5	0	1880.98	1909.37	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 86 T12	T12	Detached	South East	B 84 (84.2713636320421)	16.6	16.85	1.48	113.3	5	0	1880.98	1909.37	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 15 T13	T13	Detached	South West	B 84 (83.833448617965)	17.34	17.35	0.06	128.2	5	0	2222.55	2223.67	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 36 T13	T13	Detached	South West	B 84 (83.833448617965)	17.34	17.35	0.06	128.2	5	0	2222.55	2223.67	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 37 T13	T13	Detached	North East	A 92 (91.8887361352442)	9.4	15.97	41.14	128.2	5	-1606.39	1205.36	2046.72	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	2	SW REAR
Plot 47 T11	T11	Detached	North West	B 85 (84.9038858378805)	15.75	15.85	0.63	139.64	5	0	2199.76	2213.31	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 26 T11	T11	Detached	South East	B 85 (84.5229950730229)	16.35	16.43	0.49	139.64	5	0	2283.47	2294.25	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 85 T11	T11	Detached	South East	B 85 (84.5229950730229)	16.35	16.43	0.49	139.64	5	0	2283.47	2294.25	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 85 T11	T11	Detached	South East	B 85 (84.5229950730229)	16.35	16.43	0.49	139.64	5	0	2283.47	2294.25	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 93 1 bed gf	Flat	GF	North West	B 84 (83.935661346036)	17.4	18.42	5.54	64.19	5	0	1117.06	1182.6	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 94 1 Bed GF	Flat	GF	North West	B 84 (83.935661346036)	17.4	18.42	5.54	64.19	5	0	1117.06	1182.6	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 95 1 bed GF	Flat	GF	North West	B 84 (83.935661346036)	17.4	18.42	5.54	64.19	5	0	1117.06	1182.6	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 96 1 bed TF	Flat	TF	South East	B 83 (83.1087552553836)	19.19	20.49	6.34	50.57	5	0	970.2	1036.22	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 97 1 bed TF	Flat	TF	South East	B 83 (83.1087552553836)	19.19	20.49	6.34	50.57	5	0	970.2	1036.22	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 98 1 bed TF	Flat	TF	South East	B 83 (83.1087552553836)	19.19	20.49	6.34	50.57	5	0	970.2	1036.22	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 67 2 bed GF	Flat	GF	North West	B 84 (83.935661346036)	17.4	18.42	5.54	64.19	5	0	1117.06	1182.6	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 56 2 bed gf	Flat	GF	North West	B 84 (83.935661346036)	17.4	18.42	5.54	64.19	5	0	1117.06	1182.6	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 68 1 bed gf	Flat	GF	North West	B 84 (83.935661346036)	17.4	18.42	5.54	64.19	5	0	1117.06	1182.6	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 57 1 bed gf	Flat	GF	North West	B 84 (83.935661346036)	17.4	18.42	5.54	64.19	5	0	1117.06	1182.6	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 69 2 bed mf	Flat	MF	North West	B 85 (85.3250556359655)	14.64	16.11	9.12	64.19	5	0	939.63	1033.9	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 58 2 bed mf	Flat	MF	North West	B 85 (85.3250556359655)	14.64	16.11	9.12	64.19	5	0	939.63	1033.9	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 70 2 bed mf	Flat	MF	North West	B 85 (85.3250556359655)	14.64	16.11	9.12	64.19	5	0	939.63	1033.9	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 59 2 bed mf	Flat	MF	North West	B 85 (85.3250556359655)	14.64	16.11	9.12	64.19	5	0	939.63	1033.9	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 71 1bed mf	Flat	MF	South West	B 84 (84.2033791553042)	16.81	18.19	7.59	50.49	5	0	848.9	918.52	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 60 1 bed mf	Flat	MF	South West	B 84 (84.2033791553042)	16.81	18.19	7.59	50.49	5	0	848.9	918.52	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 72 2 bed tf	Flat	TF	North West	B 84 (84.4682757599349)	16.37	17.79	7.98	64.19	5	0	1050.59	1142.13	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 61 2 bed tf	Flat	TF	North West	B 84 (84.4682757599349)	16.37	17.79	7.98	64.19	5	0	1050.59	1142.13	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 73 2 bed tf	Flat	TF	North West	B 84 (84.4682757599349)	16.37	17.79	7.98	64.19	5	0	1050.59	1142.13	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 62 2 bed tf	Flat	TF	North West	B 84 (84.4682757599349)	16.37	17.79	7.98	64.19	5	0	1050.59	1142.13	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 74 1 bed tf	Flat	TF	South East	B 83 (83.1087552553836)	19.19	20.49	6.34	50.57	5	0	970.2	1036.22	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 63 1 bed tf	Flat	TF	South East	B 83 (83.1087552553836)	19.19	20.49	6.34	50.57	5	0	970.2	1036.22	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 64 T24	T24	End-terrace	South West	B 84 (83.7103857354685)	17.55	18.2	3.57	79.54	5	0	1395.95	1447.67	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 65 T24	T24	Mid-terrace	South West	B 84 (83.7103857354685)	17.55	18.2	3.57	79.54	5	0	1395.95	1447.67	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 66 T24	T24	End-terrace	South West	B 84 (83.7103857354685)	17.55	18.2	3.57	79.54	5	0	1395.95	1447.67	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 92 T25	T25	End-terrace	South East	B 85 (84.5648386854932)	16.11	16.67	3.36	93.24	5	0	1502.19	1554.25	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 91 T25	T25	Mid-terrace	South East	B 85 (84.5648386854932)	16.11	16.67	3.36	93.24	5	0	1502.19	1554.25	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 90 T25	T25	End-terrace	South East	B 85 (84.5648386854932)	16.11	16.67	3.36	93.24	5	0	1502.19	1554.25	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 81 T25	T25	Semi-detached	South East	B 85 (84.5648386854932)	16.11	16.67	3.36	93.24	5	0	1502.19	1554.25	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 81 t25	T25	Semi-detached	South East	B 85 (84.5648386854932)	16.11	16.67	3.36	93.24	5	0	1502.19	1554.25	Potterton	Promax Ultra	Combi 28 ErP	Decentralised whole house extract	0	
Plot 4 T8	T8	Detached	South West	B 83 (83.2605231901421)	18.16	18.24	0.44	104.36	5	0	1895	1903.81	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 5 T8	T8	Detached	South West	B 83 (83.2605231901421)	18.16	18.24	0.44	104.36	5	0	1895	1903.81	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	0	
Plot 103 T8	T8	Detached	North West	B 90 (90.0995206438992)	11.12	17.4	36.09	104.36	5	-1204.8	1160.37	1815.48	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	1.5	SE REAR
Plot 104 T8	T8	Detached	North West	B 90 (90.0995206438992)	11.12	17.4	36.09	104.36	5	-1204.8	1160.37	1815.48	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	1.5	SE REAR
Plot 106 T8	T8	Detached	North West	B 90 (90.0995206438992)	11.12	17.4	36.09	104.36	5	-1204.8	1160.37	1815.48	Potterton	Promax Ultra	Combi 40 ErP	Decentralised whole house extract	1.5	SE REAR
					1683.04	**1878.22**					**151579.6**	**169954.4**					**30.5**	

(1-DER/TER))*100 **10.8116** **percent** **reduction** **over building regulations**

12th November 2018